



# METHOD A & B APPLICATION AND PRICE ADJUSTMENT CALCULATION

2020 Asphalt Seminar | Fredericksburg



# Roller Pattern, Control Strips and Test Sections with Method A & B

#### **Roller Pattern and Control Strips:**

When, Where and How

#### **Test Sections 'aka' as Lots:**

- When, Where and How
- For both Method A and B in the Special Provision for Density Determination and
- The 2016 R&B Specification



# Roller Pattern and Control Strips


# Establishes the max achievable density for the mix for and sets the Nuclear Target for QC:

- New course of each new road way
- Combination of equipment and
- Job mix formula
- Paver pass of 6 feet and greater

#### **Key inspection points:**

- RP & CS Complete within first 1000'
- Representative of the new course
- Mat temperature is critical, RP & CS completed before mat cools to 150F
- Verify that CS cores meet specification
- The RP & CS is considered a Lot





# **Payment for Control Strips:**

**Section 315.05(e)1a Control Strip** is amended to replace the last paragraph with the following:

The control strip shall be considered a lot. If the control strip density conforms to the requirements specified in Table III-3, the Engineer will consider the control strip to be acceptable and the control strip density shall become the target control strip density.

TABLE III-3
Minimum Control Strip Density Requirements

Mixture Type	Min. Control Strip Density (%) <sup>1</sup>
SM-9.5A, 12.5A	92.5
SM-9.5D, 12.5D	92.5
SM-9.5E, 12.5E	92.5
IM-19.0A, IM-19.0D, IM-19.0E	92.2
BM-25.0A, BM-25.0D	92.2

<sup>&</sup>lt;sup>1</sup>The control strip density requirement is the percentage of theoretical maximum density of the job-mix formula by SUPERPAVE mix design or as established by the Engineer based on two or more production maximum theoretical density tests.

TABLE III-4
Payment Schedule for Failing Control Strips

r dymone constant for r dilling control carps					
% TMD	% of Payment				
Greater than 96.5	95				
92.2/92.5 <sup>1</sup> – 96.5	100				
90.0-92.1/92.41	90				
88.0-89.9	80				
Less than 88.0	75				

<sup>&</sup>lt;sup>1</sup>For SM-9.5 and SM-12.5 mixes, the minimum density value is 92.5% per Table III-3. For IM-19.0 and BM-25.0 mixes, the minimum density value is 92.2 per Table III-3.



## **Test section (lot):**

315.05 (e) 1

The Engineer will divide the project into control strips" and "test sections" for the purpose of defining areas represented by each series of tests.

#### 315.05 (e) 1 b. **Test section (lot):**

For the purposes of determining acceptance, the Engineer will consider each day's production as a lot..... The standard size of a lot will be 5,000 linear feet (five 1,000 foot sublots) of any pass 6 feet or greater made by the paving train for the thickness of the course.





# When and where to use Method A vs Method B on Paving Schedules

TABLE III-2A
Density Acceptance Methods

Density Acceptance Method to be used	Route type	Traffic Group	Minimum roadway pavement width
Method 'A' (plugs or cores)	All intersate & limited access primary     Primary & secondary with	X and higher (>=2,000 ADT)	20'
Method 'B' (nuclear guage)	<ul> <li>minimum traffic &amp; width</li> <li>Primary &amp; secondary not meeting minimum traffic &amp; width</li> </ul>	IX and lower (< 2,000 ADT)	n/a

Page 16 of 21 Schedule: PM-7B-19 Madison Co.

State Project Number: PM7B-967-F19, P401

Route: 29 (R-VA US00029SB) Milepost From: 5.64 Rt. 733

Subdivision: S PCN: M719PMB112989 UPC: 112989

Traf Grp: XVII Milepost To: 8.41 Rt 634

From Intersection: 5.04 Miles: Oak Hill Ct; Rt. 733E/W (Madison County)

From Offset: 0MI From X/Y Coordinates: 38.34785, -78.28435

To Intersection: 8.41 Miles: Oak Park Rd, Washington St, Rte 634N/S (Madison Co);

To Offset: 0MI To X/Y Coordinates: 38.37922, -78.25285

Public Comments:

Item Code & Description	Detail	Len(mi)	Wid(ft)	Dep(in)	Gal/SqYd	Lbs/SqYd	Quantity	UOM
10700 - RUMBLE STRIP, ASPHALT	R6 @ 12" wide						25595	LF
16350 - ASPHALT CONC. TY. SM-12.5A	4' Right Shoulder 3' Left Shoulder	2.77	7	2			1251.3	TON
16350 - ASPHALT CONC, TY, SM-12,5A	Connections and Turn lanes						367	TON
16350 - ASPHALT CONC. TY, SM-12,5A		2.77	24			230	4485.18	TON




#### **Method A Test Sections:**

**Required Testing:** 

**QC** via Two Nuclear Locations (Yellow)

Acceptance via One Core Location per 1000' sub-lot (Black)

Each day's production is a Lot – made up of test sections and sub lots. Pay adjustments are calculated based on the materials with in the lot








#### **Method B Test Sections:**

Same as the 2016 Road and Bridge Specification for Section 315

**Required Testing (per 1000'):** 

**Two Nuclear Locations (Yellow)** 







# Applying price adjustments to Test Sections (Lots):

#### 2016 Road and Bridge Section 315.05:

The tonnage of each lot will be based on the lot's width and length and the mixture application rate as designated in the Contract or as revised by the Engineer. Payment will be made in accordance with **Table III-4**.

#### **The Special Provision for Density Determination:**

The tonnage of each lot will be based on the lot's <u>width</u> and <u>length</u> and the <u>mixture application rate as designated in the Contract</u> or as revised by the Engineer. Payment will be made in accordance with the requirements of **Table III-4A** (or **III-4B** for **Method B**).




#### **Test Section Widths:**

Define the width of the Lot Defines the width of the

testing area and random numbers

Tests are not conducted within 12"/18" of application width



# **Lot Length and Turn** Lanes

The Engineer will divide the project into "control strips" and "test sections" for the purpose of defining areas represented by each series of tests.

The Engineer needs to determine whether these areas are part of the lot, and if so then they need to be tested, i.e. select random numbers and test locations within these lengths as well:

When paving is less than 3,000 feet, that day's production will be combined with the previous day's production or added to the next day's production to create a lot as described below





# Calculating Lot tonnages for Price Adjustments TL-59A L(4936')\*W(13')/9sqyd \* 230lbs/sqyd/2000 = 819.92 Tons

# Asphalt Concrete Density Acceptance Test Report - Method A Acceptance by Plugs/Cores

Production Date:	4/23/19	Route & Dire	ection:	RT 33	Lane(s):	EBL/LEFT
Project/Schedule Number:	PM7B-967-F19	County:		Albemarle	Paving Contractor:	SLWCO
Test Section (Lot) #:	5	From (Statio	n, MP):	.4 W. Rt 625	To (Station, MP):	.75 MI. E. Rt. 638
Total paved length (ft):	4,936	Application	Width (ft):	13	Application Rate (lbs/sy):	230
Calculated tonnage:	819.92	Asphalt Prod	ucer:	SLWCO	Asphalt Plant:	RUCKERSVILLE
Asphalt Mix Type:	SM-12.5 A	Job Mix ID:		7024-2019-32	_	
Control Strip Information: 1. Control Strip Numb	per and Date:CS	2 4/17/19	2. CS Density:	148.2 lbs/ft³	Nuclear Gauge Serial #:	64966
3. Min Longitudinal Jo	oint Density:	140.79	lbs/ft³ (= 95% C	S Density)		
Acceptance Testing Results By	Plugs/Cores:	Daily Gmm:	2.578	Plant Lot & Sample #(s) for	Gmm testing: 201	9-01 Sub 7 & 8



### **Core Results from the same TL-59A**

	3. Min Lon	igitudinal Jo	int Density:	140.	79	lbs/ft³ (= 95% (	CS Density)	-				
Accept	tance Testing	Results By	Plugs/Core	s:	Daily Gmm:	2.578	Plant Lot & San	mple #(s) for (	Gmm testing:	2	019-01 Sub 7 &	8
Sub lot	Distance (ft)	Offset (ft)	Thickness (in)	Weight in Air [A]	Weight in H2O [B]	SSD Weight [C]	Volume (C-B)	Gmb (A/(C- B))	%Gmm	Bonus Eligible	Longitudinal Left (lbs/ft <sup>3)</sup>	Joint Density Right (lbs/ft <sup>3</sup>
1	256	4	2"	902.1	535.1	902.7	367.6	2.45	95.0%	1	142.8	
2	1752	5	2"	1084.1	639.5	1085.1	445.6	2.43	94.3%	1	145.1	
3	2149	8	2"	1065.5	631.2	1066.4	435.2	2.45	95.0%	1	146.5	
4	3303	9	2"	932.4	548.4	933.2	384.8	2.42	93.9%	1	145.1	
5	4926	6	2"	1174.1	687	1175.6	488.6	2.40	93.1%	1	144.6	
6												
7				1 6 6								
	Pay Factor fro	om \$315HP1	Table III-4A:	105%		Averages:	,	2.430	94.3%	100.0%	Percent of sub l bonus criteria	ots meeting
	Level II ician:	Susan	Casa	dy	Comments:					Date:	4/23/19	
-11.5PC												



# Total shipped tons from that day's paving = 976.61

# VIRGINIA DEPARTMENT OF TRANSPORTATION WEIGHPERSON'S SUMMARY

This is to certify that	S.L. Williamson Company, Inc	(24) Ruckersville	
Shipped the following	materials on the below reference	e date.	
Shift Start Date:	4/23/2019 6:00 AM	End Date:	4/23/2019 6:00 PM
Project:	PM7B-967-F19,P401		UPC ID: 112989
Route:	33		
County:	Greene		
Acceptance Program:	X Quality Assu	rance	Modified Acceptance Program
Type Material:	Superpave SM-12.5A (50 gyra	ation)	
Job Mix ID:	7024-2019-32	Identifier:	
Lot Number:	201901	Order:	
No. Loads:	45	•	
Total English Tons:	976.61		



## Reconciling the tonnage:

Calculated Tonnage from the Lot Testing – 819 tons

Shipped Tonnage from the TL-102s – 976 tons

What gives? Where did the 157 tons go?

Connections, crossovers, gore areas.. Double check your dimensions and lift thickness

Page 13 of 21 Schedule:PM-7B-19 Greene Co.

State Project Number: PM7B-967-F19, P401

Route: 33 (R-VA US00033EB) Milepost From: 2.59 .4 W. Rt. 625

Subdivision: B PCN: M719PMB112989 UPC: 112989

Traf Grp: XIII Milepost To: 5.15 .75 MI. E. Rt. 638

From Intersection: 2.99 Miles: Goose Pond Rd; Rt. 625N/S (Greene County)

From Offset: -0.4MI From X/Y Coordinates: 38.34347, -78.51075

To Intersection: 5.09 Miles: Dunivan Ln; Powell Mountain Rd; Timber Dr; Ramp Intersection

To Offset: 0.06MI To X/Y Coordinates: 38.32168, -78.47661

Public Comments:

Item Code & Description	Detail	Len(mi)	Wid(ft)	Dep(in)	Gal/SqYd	Lbs/SqYd	Quantity	UOM
16350 - ASPHALT CONC, TY, SM-12.5A	Connections						92	TON
16350 - ASPHALT CONC. TY. SM-12.5A		2.56	26			230	4490.58	TON
16522 - FLEXIBLE PAVE.PLANING 0"-2"		2.56	26	2			39048.53	SY



## **Applying Price Adjustments on the total**

Calculated Tonnage from the Lot Testing – 819 tons is subject to price adjustments, in this case a 5% bonus

- Method A
- Method B and
- 2016 Road and Bridge Specification

While the 157 tons is paid for at the unit bid price



## **Method A and B Pay Tables**

Method A Bonus Language
If a minimum of 80% of each lot's core/plug samples is no lower than 92.5% of TMD for Surface Mixes and 92.2% of TMD for Intermediate and Base Mixes and the lot average results in 100%

payment, then the Engineer will increase the unit bid price for AC mixture by five (5) percent.

TABLE III-4A
Payment Schedule for Method A Lot Densities

. ajinan aana isi mama	
% TMD	% of Payment
Greater than 96.5	95
$92.2^{1}/92.5^{2} - 96.5$	100
90.0 <b>–</b> 92.1 <sup>1</sup> /92.4 <sup>2</sup>	90
88.0 – 89.9	80
Less than 88.0	75

<sup>&</sup>lt;sup>1</sup>For Intermediate and Base Mixes, the minimum TMD percentage is 92.2 per Table III-3

TABLE III-4B
Payment Schedule for Method B Lot Densities

% of Target Control Strip Density	% of Payment
Greater than 102.0	95
98.0 to 102.0	100
97.0 to less than 98.0	95
96.0 to less than 97.0	90
Less than 96.0	75


<sup>&</sup>lt;sup>2</sup>For Surface Mixes, the minimum TMD percentage is 92.5% per Table III-3

#### **Problems that arise**

Paved length – 8316'
Calculated Tonnage
Reported as – 1064.86
but calculates to 1219.7


Testing only accounted for 7500'
We left 815 feet untested


TL-102 tonnage reported as 1064.86





# How to handle partial sub-lots at the end of the day





Sub lot	Distance	Offset	Weight in Air [A]	Weight in H2O [B]	SSD \
- 1	1156	4	1091.	628.7	109;
2	1526	2	1068.5	<u>620.4</u>	1065
3	4499	2	939.6	538.4	940
4	4815	3	938.0	538.9	939
5	6375	9	894.3	514.3	894
6	8606	6		18	
7	10246	10			



# Thank You and have a great and Safe paving season!

