

RAPID BRIDGE REPAIR WORKSHOP

PREFABRICATED BRIDGE ELEMENTS

MAY 22, 2009

BY: CLAUDE S. NAPIER, Jr., P.E.

Senior Structural Engineer

FHWA Resource Center Structures Technical Service Team



OUTLINE

- Introduction
- Buzz Words
- Major Initiatives
- ACTT Approach
- Highways For Life (HfL)
- Prefab Bridge Elements/System Scan
- Prefab Scan Technologies

OUTLINE

- Innovative Use Of Prefabricated Systems
- Success Stories Of US Prefabricated Bridges
- Survey Of State Bridge Engineers
- Decision Making Framework
- Connection Details For Prefabricated Bridge Elements & Systems
- Summary

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

3

TRAFFIC CONGESTION

- The nation's 4 Million mile highway system is considered most extensive and heavily traveled highway network
- Unprecedented increase in traffic volumes coupled with our aging infrastructure have caused highway construction activities to intensify



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

4

LANE CLOSURES

- It is not just the congestion, it is the safety
- Annual loss of 40,000 lives due to accidents
- \$63 Billion annual loss due to congestion



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS


5

Present and Future Challenges

- Aging Infrastructure....1/3 in Poor Condition
- 70% Increase in Freight Tonnage Between 1998 and 2020
- 90% of urban interstate expected to exceed/approach capacity by 2020

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

6



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

7

BUZZ WORDS

Get In

Get It Done (& Done Right)

Get Out

Stay Out

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

8

MAJOR INITIATIVES

- Accelerated Construction Technology Transfer (ACTT)
- Highways For Life (H4L)
- AASHTO/FHWA Prefab Bridge Scan
- Innovative Use Of Prefabricated Systems
- PBES Decision Making Framework
- Connection Details For Prefabricated Bridge Elements & Systems

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

9

ACTT APPROACH

- Encourage the development of strategies that generate positive change.
- Create a framework for informed consideration of innovations.
- Facilitate removal of barriers to innovation
- Improve motorist and worker safety.
- Advocate continuous quality improvements.

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

10

ACTT's GOAL

- ACTT Addresses The Construction Time And Traffic Congestion Concerns Of Today's Large, Complex Multi-phase Projects

Systems or Concepts to Accelerate Construction

- Ground up
- Material Choices
- Equipment
- Prefabrication
- Access Logistics
- Pre-assembly
- Pre-purchase & Fabricate

Systems or Concepts to Accelerate Construction

- Off-site Assemble
- Off site roll-in/lift-in
- Incremental Launching
- Longitudinal vs Transverse Components

What is Accelerated Bridge Construction?

- Fast track process
- Prefabricate bridge elements and systems
- Elements constructed off-site
- Lift into place
- Reduce on site construction time and traffic impact

Why Now?

- One Third of US Bridges need Rehabilitation or Replacement
- Lane closure can cause significant traffic and economical impact
- Minimizing traffic impact is a crucial issue

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

15

Advantages

- Reduces on-site construction time
- Minimizes traffic disruptions
- Improves work zone safety
- Minimizes environmental impact
- Improves constructibility
- Increases product quality and
- Lowers life-cycle-costs

GET IN, GET OUT, STAY OUT

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

16

Reduces On-Site Construction Time

- Less time spent on-site
- Traditional tasks can be done off-site
- Minimal impact from weather conditions



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

17

MINIMIZES TRAFFIC IMPACTS

- Minimizes traffic delay and community disruption

I-59 and I-65 Interchange, AL



US 59 under Dunlavy, TX

- Reduces detours, lane closures, and narrow lanes

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

18

IMPROVES WORK ZONE SAFETY



Meylan Pedestrian Bridge, France

- Minimizes work near traffic and power lines, at high elevations, or over water.

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

19

Minimizes environmental impact

- Keep heavy equipments out of sensitive environment



Linn Cove Viaduct, NC

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

20

Improves Constructibility

- Minimal impact from environmental constraints
- Relieves from constructibility pressure.



San Mateo-Hayward Bridge, CA

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

21

Increases quality

- Prefabricated in a Controlled environment
- Increases quality control



George P. Coleman Bridge, VA

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

22

HIGHWAYS FOR LIFE (HfL)

Long Lasting

Innovative

Fast Construction

Efficient and Safe

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

23

HIGHWAYS FOR LIFE (HfL)

- Utilize Proven Successes
- Involve New Stakeholders
- Do The “Never Been Done”
- Be Bold And Audacious

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

24

HfL VISION AND GOALS


- Improve Safety
- Reduce Congestion Due To Construction
- Improve Quality

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

25

IT'S BEEN DONE

**Coleman Bridge
Yorktown, VA**




RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

26

IT'S BEEN DONE


**I-95 over James River Bridge
Richmond, Virginia**



**RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS**

27

IT'S BEEN DONE



**Baldorioty de Castro Avenue Bridges
San Juan, Puerto Rico**

**RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS**

28

PREFAB BRIDGE ELEMENTS/SYSTEMS SCAN

- MISSION STATEMENT
- TEAM MEMBERS
- SCAN COUNTRIES
- TOPICS OF INTEREST
- TECHNOLOGIES

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

29

MISSION STATEMENT

- To investigate and document project experiences with prefabricated bridge elements and systems in Japan and selected European countries with emphasis on accelerated technique to replace existing or construct new routine bridges.

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

30

TEAM MEMBERS

FHWA:

- Benjamin Tang, Co-Chair
- Claude Napier, Jr., VA
- Barry Brecto, WA

Academia:

- Eric Matsumoto, CSUS, CA

Industry:

- Henry G. Russell, IL
- Shri Bhide, PCA, IL

State DOTs

- Mary Lou Ralls, Co-Chair, TX
- Harry Capers, NJ
- William Nickas, FL
- Dan Dorgan, MN

National Association of County Engineers:

- Eugene Calvert

Contractor: John O'Neill, ATI

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

31


SCAN COUNTRIES




Netherlands



Belgium



Japan



France



Germany

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

32

TOPICS OF INTEREST

- Minimized traffic disruption (Congestion)
- Improved work zone safety
- Minimized environmental impacts
- Improved constructability
- Improved product quality
- Lower life-cycle costs

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

33

PREFAB SCAN TECHNOLOGIES

- LONGITUDINAL & TRANSVERSE LAUNCHING
- U-SHAPE SEGMENTS WITH TRANSVERSE RIBS
- HYBRID STEEL DECK FORMS
- FULL DEPTH PRETENSIONED PRECAST DECK PANELS
 - GROUT POCKETS AND TRANSVERSE JOINTS
 - LOOP BAR JOINT AND CLOSURE POUR

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

34

PREFAB SCAN TECHNOLOGIES

- SPER SYSTEM
- MULTIPLE LEVELS OF CORROSION PROTECTION USING OVERLAYS
- TEE AND BOX BEAMS
- PARTIAL-DEPTH PRECAST DECKS ON STEEL BEAMS
- SELF-FROPELLED MODULAR TRAILERS
 - MOVING WHOLE STRUCTURES

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

35


CONTINUOUS LAUNCHING



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

36


TRANSVERSE LAUNCHING



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

37

U-Shaped Precast Segments




U-Shaped Precast Segments with Transverse Ribs




Hybrid Steel Deck Forms



Full-Depth Pretensioned Precast Deck Panels



Grout Pockets and Transverse Joints




LOOP BAR JOINT AND CLOSURE POUR




RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

43

SPER System



SPER System




Multiple Levels of Corrosion Protection Using Overlays





PARTIAL-DEPTH PRECAST DECKS ON STEEL BEAMS



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

Self-Propelled Modular Trailers



SELF-PROPELLED MODULAR TRAILERS (SPMT)

One-Man Operator



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

50

MOVING & ERECTING STRUCTURES

- Mammoet
- Sarens



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

51

MOVING A WHOLE SUPERSTRUCTURE



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

52

Badhoevedorp, Netherlands



April 2004
Prefabricated
Bridges
International
Scan

Superstructure Roll-In:
390-ft Length,
3300 M Tons,
2 Hours to Move,

1 Weekend Road Closure

**RAPID BRIDGE REPAIR
PREFABRICATED**




MOVING THE WHOLE BUILDING



**RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS**

54


BRIDGE SCHEMATIC



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
 PREFABRICATED BRIDGE ELEMENTS

55

MOVEMENT OPERATION



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
 PREFABRICATED BRIDGE ELEMENTS

56

MOVED BRIDGE WITH SPMT



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

57

BRIDGE TO BE MOVED



Horizontal Sliding
with strand jacks

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

58


Prefabricated Elements

- Decks
- Total superstructure systems
- Bent caps
- Columns
- Total substructure systems
- Foundation
- Total prefabricated bridges

Prefabrication Focus: Innovative Elements & Systems

- **Superstructures**
 - **Deck Panels:** Full-Depth
 - **Beams:** More Efficient Shapes
 - **Total Superstructure Systems:**
Composite Units, Truss Spans
- **Substructures**
 - **Caps**
 - **Total Substructure Systems:**
Abutments, Cap/Column(s), Pier(s)
- **Totally Prefabricated Bridges**


Superstructure Prefabrication



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

61


Superstructure Prefabrication with Continuity



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

62


Precast Piers



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

63


Precast Abutments



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

64

Total Bridge Prefabrication



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

65

Prefabricated Bridge Success Stories

A few examples...




RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

66

SR-433 Lewis and Clark Bridge Columbia River, WA/OR–2004

Replaced 3900 ft of
deck using SPMTs
during 120 nights
plus four weekend
closures ...



... with no impact to
rush-hour traffic

**RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS**

67



Lewis and Clark
Bridge, SR 433
over Columbia
River – 2004

103 full-width,
full-depth precast
lightweight concrete
panels, each 36-ft wide x
20-45 ft long



**RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS**

68

Lewis and Clark Bridge Deck Replacement Construction Costs

- ✓ Number of bidders 6
- ✓ 2nd lowest bid \$ 29.2 M
- ✓ Low Bid \$ 18.0 M
- ✓ Savings – 38 % = \$ 10.8 M
- ☑ Closures: Only 120 nights & 4 weekends
- ✓ Engineer's Estimate \$ 28.8 M

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

69

I-95 James River Bridge Richmond, VA – 2002



... with no lane
closures during
rush-hour traffic

100 superstructure spans
replaced in 135 nights



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

70



Virginia's Superstructure Replacement of
I-95 James River Bridge

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

71

James River Bridge Superstructure Replacement Construction Costs

| | |
|------------------------------|-----------------|
| ✓ Engineer's Estimate | \$ 48.5 M |
| ✓ Number of bidders | 5 |
| ✓ 2nd lowest bid | \$ 44.9 M |
| ✓ Low Bid | \$ 43.4 M |
| ✓ Savings – 11 % = | <u>\$ 5.1 M</u> |

Closures: Only 135 nights

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

72

SH-66 Lake Ray Hubbard Bridge near Dallas, TX – 2003



...proposed by
the Contractor

43 identical precast
concrete bent caps ...



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

73

SH-66 Lake Ray Hubbard Bridge near Dallas, TX – 2003



Precast bent caps –
the best solution for
site conditions



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

74

Lake Ray Hubbard Bridge with Precast Bent Caps Construction Costs

| | |
|------------------------------|-----------------|
| ✓ Engineer's Estimate | \$ 48.2 M |
| ✓ Number of bidders | 8 |
| ✓ 2nd lowest bid | \$ 43.1 M |
| ✓ Low Bid | \$ 40.9 M |
| ✓ Savings – 15 % = | <u>\$ 7.3 M</u> |

Onsite Time Savings: 215 Days

**RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS**

75

WELLS STREET BRIDGE, CHICAGO – 2002



111-ft long, 25-ft high, 425-ton truss span installed over a weekend

**RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS**

76

Newark International Airport Monorail



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

77

I-287 Cross Westchester Viaduct, New York



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

78

SH 66 over MITCHELL GULCH, COLORADO - 2002



**RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS**

79

Baldorioty de Castro Avenue San Juan, Puerto Rico – 1992



Two 700-ft and two 900-ft bridges, each installed in 21-36 hrs

Church Street Bridge, Connecticut

- 320- Feet Truss Span
- 50-feet High and 60-feet Wide
- Total Weight = 850 T
- Lifted and placed in one night
- Minimized Rail Disruptions



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

81

Hyper Build Project Bridges on Route 1, New Jersey

- August 17, '05
o 2 PM, Sections Arrive at Airport
- August 27, '05
o 4:10 – 9:30 AM – Removing Old Deck




RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

82

Hyper Build Project Bridges on Route 1, New Jersey

- August 28, '05
 - o 1:40 AM, Setting Beams in Place
 - o 11:55 AM, Installing New Deck
- Compressed Schedule From 24 Months to 3 Weekends
- Cost Savings - \$2.5M



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

83

I-45 Pierce Elevated, Texas

- Prefabricated Caps on 226 Spans – 190 Days vs. 1 ½ Years



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

84

SH 36 Over Lake Belton, Texas


- Repetitive construction over water
- Precast Columns
- Precast Caps



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
 PREFABRICATED BRIDGE ELEMENTS

85

ABC Scoreboard



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
 PREFABRICATED BRIDGE ELEMENTS

86

Prefabricated Bridge Benefits

- ✓ Minimizes traffic disruptions
- ✓ Improves work-zone safety
- ✓ Minimizes environmental impact
- ✓ Improves constructability
- ✓ Improves product quality
- ✓ Lower costs

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

PREFABRICATED BRIDGE BENEFITS

- ☑ **Faster**
- ☑ **Safer**
- ☑ **Better Quality**
- and ...**
- ☑ **Lower Cost!**

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

88



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

89

Prefabrication – Improved Quality & Lower Life-Cycle Costs – to “Stay Out”

- Controlled environment
 - o Reduced dependence on weather
 - o Established materials suppliers for consistent quality of materials
 - o Standardized plant operations for consistent quality of production
 - o Optimum concrete curing

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

90

Prefabricated Bridges to Accelerate Construction

Survey to Sample State Bridge Engineers

Question: Barriers to routinely install PBES in hours or days?

Summary: Barriers

- Lack of education / training / experience (13)
- Lack of standards & specifications (13)
- Concerns about durability or details (12)
- Higher cost & limited resources (9)
- Lack of perceived need for speed (8)
- Construction industry not geared up for prefab (7)

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

91

Prefabricated Bridges to Accelerate Construction

Survey to Sample State Bridge Engineers

Question: What would help most to use PBES?

Summary: Needs

- Education / training / more projects (7)
- Design & construction standards & specifications (6)
- Additional research/development to address concerns about durability or details (5)
- Competitive cost & additional funding (6)
- Appropriate projects that require speed (4)
- Fabrication & construction equipment & methods (5)

92

Current Activities to Address the Needs

- Education / Training
 - Meetings, workshops, conferences
 - Decision-Making Framework
 - Manual on Use of SPMTs to Move Bridges (on website)
 - Manual on PBES Connection Details (June/July 2009)
- Projects / Details, Standards, and Specifications
 - Online resources on prefabricated bridges
 - <http://www.fhwa.dot.gov/bridge/prefab>
 - Projects – details, contacts, standards, specifications
 - Research
 - Publications
- Technical Advancements, e.g., on durability issues
 - NCHRP and other research projects on connections and other details
 - Available innovative construction equipment

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

93

Framework for Prefabricated Bridge Elements and Systems (PBES)

Decision-Making Framework

FHWA Team

Benjamin Tang (Retired)

Vasant Mistry

Helene Bowman

Gary Jakovich (EFLD)

Claude Napier

Eric Gabler

Raj Ailaney

Byron Lord

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

94

Framework for PBES

Decision-Making

Users

- ✓ Decision makers for bridge type
- ✓ Implementers
 - ✓ Designers
 - ✓ Project Managers

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

95

Framework for PBES

Decision-Making – In General

- ✓ PBES are faster
- ✓ PBES are safer
- ✓ PBES have lower initial costs
 - ✓ Due to significantly reduced traffic control, risks, environmental impacts, user delay costs
- ✓ PBES are better
 - ✓ Due to improved quality control off-site and off-the-critical-path fabrication

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS


96

Framework for PBES Decision-Making – Specific Project Considerations

- ✓ Faster
- ✓ Better
- ✓ Safer
- ? Is prefabrication the best solution for this specific project ?
 - ? Lower initial costs ?
 - ? Long lasting ?

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

97



Decision-Making Matrix

Example Questions

| Question | Yes | Maybe | No |
|---|-----|-------|----|
| High traffic volume? | | | |
| Emergency replacement? | | | |
| ... | | | |
| Worker safety concerns? | | | |
| ... | | | |
| High daily traffic control costs? | | | |
| ... | | | |
| <div style="display: flex; justify-content: space-between; align-items: center;"> <div> RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP PREFABRICATED BRIDGE ELEMENTS </div> <div style="background-color: black; color: white; padding: 2px 5px;">99</div> </div> | | | |

Future Direction

- Widespread use of Accelerated Construction
- Engineering the solution to satisfy unique constraints
 - Traffic disruptions, work zone safety, environmental impact, constructability, improve quality, lower life cycle costs
- Catalogue of Connection Details
- Develop Manual on Prefabricated Systems
- Self Propelled Modular Transport (SPMT) – How To Manual?
- More owner / industry / consultant / academia / public partnerships for optimum solutions

You've heard it said ...

*“IF YOU WANT IT FAST
IT WON'T BE GOOD
IT WON'T BE CHEAP
IF YOU WANT IT GOOD
IT WON'T BE CHEAP
IT WON'T BE FAST
IF YOU WANT IT CHEAP
IT WON'T BE FAST
IT WON'T BE GOOD*

PICK ONE”

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

Connections Details for Prefabricated Bridge Elements and Systems

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

Roadblocks to Accelerated Construction

- The primary concerns that owner agencies have with respect to adopting accelerated construction techniques are:
 - o Need for Quality Details
 - o Durability
 - o Design Methodologies and Training
 - o Construction Methodologies

“Connections for Prefabricated Bridge Elements and Systems”

- FHWA has initiated a project to develop this manual
- This publication is intended to provide information that will go a long way to answering all four of the previous concerns.
- Focus on details that have been used in the past.

Connection Details for Prefabricated Bridge Elements and Systems

Project Goals

- Gather details of **Connections** that have been used on accelerated bridge construction projects
- Investigate transfer of technology from other markets into the bridge market
 - o Parking Garages
 - o Stadiums
 - o Buildings

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

105

All details needs to pass a critical test before being published in the document:

- o Does the connection result in a rapid construction process?
- o Does the connection transmit the forces between elements effectively?
- o Is the connection durable?
- o Has it performed well under traffic and in an exposed environment?
- o Is it cost effective and easy to construct?
- o If a process or connection is proprietary, can it be incorporated into numerous projects without producing contracting issues?

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS


106

Source of Data

- State DOT's
 - Questionnaires sent via e-mail
- Federal Agencies
- International Organizations
- Researchers (previous and current)
- Producers
 - Questionnaires sent via e-mail

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

107



108

Connection Data Sheets


Connection Details for Prefabricated Bridge Elements **Federal Highway Administration**

Organization: Texas Department of Transportation Phone Number: 512-416-2279
 Contact Name: Lloyd M. West, P.E. E-mail: lloyd@tdot.state.tx.us
 Address: 1112 E. 18th Street Detail Classification: Level 1
 Austin, TX 78704

Components Connected: Precast Pier Cap to Cast-in-place Concrete Column

Name of Project where the detail was used: _____

Connection Detail: Manual Reference Section 3.3.5.1.1



1 of 2 See reverse side for more information on this connection.

Connection Details for Prefabricated Bridge Elements **Federal Highway Administration**

Organization: Texas Department of Transportation Phone Number: 512-416-2279
 Contact Name: Lloyd M. West, P.E. E-mail: lloyd@tdot.state.tx.us
 Address: 1112 E. 18th Street Detail Classification: Level 1
 Austin, TX 78704

Components Connected: Precast Pier Cap to Cast-in-place Concrete Column

Name of Project where the detail was used: _____

Description, comments, specifications, and special design procedures:



What forces are the connection designed to transmit? (check 'x' in appropriate boxes)
 Shear ☒ Moment ☒ Compression ☐ Tension ☒ Torsion ☒

What year was this detail first used? _____ Condition at last inspection (if known) _____
 How many times has this detail been used? _____ Year of last inspection _____
 Would you use it again? ☒ (yes/hold/maybe) ☐ (no)

On a scale of 1 to 10, how would you rate the performance of this connection in the following categories?
 Speed of Construction ☐ (0 very slow, 10 very fast) When compared to conventional construction
 Constructability ☐ (0 extremely making connection, 10 went together easily)
 Cost ☐ (0 expensive, 10 cost effective) When compared to other connection methods
 Durability ☐ (0 not durable, 10 very durable)
 Inspection Access ☐ (0 no access, 10 easily inspected)
 Future Maintenance ☐ (0 will need maintenance, 10 no maintenance anticipated)

2 of 2 See reverse side for more information on this connection.

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP PREFABRICATED BRIDGE ELEMENTS

109

Grouted Splice Connectors


- Emulates a reinforcing steel lap splice
- Three companies – non-proprietary
- Used in precast parking garages and stadiums



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP PREFABRICATED BRIDGE ELEMENTS

110


Precast Piers



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP PREFABRICATED BRIDGE ELEMENTS

111

Precast Decks on Concrete Beams



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP PREFABRICATED BRIDGE ELEMENTS

112




FRP Decks

Section A-A


RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

114

Partial Depth Deck Forms



NORMAL GRADING DETAIL ①




SHOWING STEEL BEAMS

**RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS**

115


Total Bridge Prefabrication



**RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS**

116

Rt. 15/29 (SBL) Bridge Superstructure Replacement and Roadway Widening



Existing Bridge Elevation


RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
 PREFABRICATED BRIDGE ELEMENTS

117

Prior to Construction



West side view of SBL
 bridge prior to
 construction



East side view of SBL
 bridge
 prior to construction

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
 PREFABRICATED BRIDGE ELEMENTS

118

Project Information

- Location: The Route 15/29 (SBL) Bridge Superstructure Replacement and Roadway Widening Project over Broad Run is located in Prince William County, 0.55 Mile North of Route 215.
- Scope: Work includes replace and widen existing bridge superstructures with offsite-fabricated superstructure segments, substructure concrete widening and repairs, re-alignment and approach work.
- Superstructure: 3-Span, Concrete T beam, Simply Supported
- Substructure: Wall type piers and abutments
- Year Built: 1952
- ADT: 25,000
- Condition: Structurally deficient and functionally obsolete.

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

119



Project Limits



Project limits within the Buckland Historical
District and the Mosby Heritage Area


RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

120



Lessons Learned


Conflicts With Beams



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
 PREFABRICATED BRIDGE ELEMENTS

123


Revised Construction of Span A



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
 PREFABRICATED BRIDGE ELEMENTS

124

Completed Structure



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

125

High Water



Before and after photos of high water after heavy rains
(10') in May 2008

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

126



Damages caused by heavy rain after
installation of cofferdam (port-a-dam)
RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

127



Installation of an additional Cofferdam at Pier 1 needed as a
result of high water to complete formwork and concrete pour

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

128

Environmental Demolition Shield



Installation of demolition shield

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

129

Weight Limitations Hand Rails Removed



Removal of existing handrails to reduce weight during the removal of segments

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

130

Steel Beams – Galvanization and Shipping



- Steel beams after galvanizing and shipment to Coastal Precast Systems, Inc.

**RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS**

131

Coastal Prefabricating Modular Deck Units




**RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS**

132

Revised Construction Sequence

Revised MOT Plan for Weekend Closures



**RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS**

133



**RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS**

134

Placing Asphalt at the Abutment and Sealing Deck Joints



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

135

Completed Structure with Asphalt Overlay



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

136

Project Schedule

- Gather information
 - Fall 2006 through Spring 2007
- Visit states that are leaders in accelerated bridge construction
 - Winter 2007
- Develop manual
 - Summer/Fall 2007
- Complete Manual
 - Summer 2008

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

137

Project Delivery

- The document will be available for all owners and designers for use in future accelerated bridge projects
 - Website will be established on the FHWA Highways for Life Website

www.fhwa.dot.gov/hfl/

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

138

Available Resources

✓ **Learn more:**

- **www.fhwa.dot.gov/bridge/prefab**

✓ **Tools:**

- ✓ Decision-Making Framework for the Use of Prefabricated Bridges
- ✓ Connection Detail Catalog, How to SPMT manual
- ✓ Specifications for Prefabricated Bridges

✓ **FHWA Contacts:**

FHWA Office of Bridge Technology and Resource Center

- ✓ **Vasant Mistry, Raj Ailaney**

**RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS**

139

AVAILABLE ONLINE RESOURCES

- ✓ General Information
<http://www.fhwa.dot.gov/bridge/prefab/>
- ✓ Projects constructed to date
<http://www.fhwa.dot.gov/bridge/prefab/projects.htm>
- ✓ Publications
<http://www.fhwa.dot.gov/bridge/prefab/pubs.htm>
- ✓ Research
<http://www.fhwa.dot.gov/bridge/prefab/research.htm>
- ✓ Calendar of upcoming events
<http://www.fhwa.dot.gov/bridge/prefab/calendar.htm>
- ✓ Virginia Division Website
<http://www.fhwa.dot.gov/vadiv/>

**RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS**

140

**Rapid
Construction**

High Quality

Low Cost

You can have any two

We suggest speed & quality

However: Elimination of temporary bridges can
offset additional cost of rapid construction

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

141

ACCELERATED CONSTRUCTION INITIATIVES


- LEAVE YOU WITH THREE (3) THINGS
 - THINK OUT-OF-THE-BOX.
 - BE BOLD AND AUDACIOUS.
 - NEEDS EARLY INVOLVEMENT IN PLANNING AND DESIGN PHASES.

RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

142

QUESTIONS?

THANK YOU



RAPID BRIDGE REPAIR TECHNIQUES WORKSHOP
PREFABRICATED BRIDGE ELEMENTS

143