

CAST-IN-PLACE CONCRETE SLAB SPANS
ESTIMATED QUANTITIES AND INDEX OF SHEETS

NOTES TO DESIGNER:

ESTIMATED QUANTITIES:

Complete the ESTIMATED QUANTITIES tables in accordance with Manual of the Structure and Bridge Division, Volume V – Part 2, Chapter 3. Complete superstructure reinforcement pay item by adding the Class I, II or III of corrosion resistant reinforcing steel required. For additional information on corrosion resistant reinforcing steels (CRR), see Structure and Bridge Division Memorandum (current IIM-S&B-81). Additional Lump sum (i.e. Mobilization, Construction Surveying, Dismantle and Remove Existing Structure, etc.) pay items may also be required for project specific requirements.

Additional items may be required for maintenance of traffic, cofferdams for construction of abutments and/or piers and environmental items such as silt fence, siltation excavation and dewatering basin. Roadway items may also be required for bridge approaches and will have to be accounted for on this sheet.

INDEX OF SHEETS:

Complete the INDEX OF SHEETS in accordance with Manual of the Structure and Bridge Division, Volume V – Part 2, Chapter 3.

SUBSTRUCTURE LAYOUT:

If a substructure layout is required, it should be shown on this sheet.