

State of the Practice

- The importance of proper dowel alignment is widely recognized, but it could not be verified effectively
- Many agencies specify strict alignment tolerances
 - Tolerance on rotation ranges from 3 mm (1/8 in) to 13 mm (1/2 in) for 457-mm (18-in) dowels
 - Typical tolerance is 10 mm (3/8 in)
- Acceptance is based on limited number of cores



MIT Scan-2 Stirs Up All Kinds of Trouble

ARA

- MIT Scan-2 measures dowel alignment with unparalleled level of efficiency and accuracy
 - What to do with all the data generated
 - Problems that went unnoticed in the past are being detected How bad is bad?
- Limitations of existing specifications on dowel placement tolerances:
 - Based on limited laboratory testing and analytical evaluation
 - Not verified with field performance



xpanding the Realm of Possibility

MIT Scan-2



- Device designed specifically for the measurement of dowel bar position and alignment
 - Developed by Magnetic Imaging Tools, GmbH
 - Based on the principles of pulse induction

ARA

Expanding the Realm of Possibility

Advantages

- Works on fresh or hardened concrete
- Real-time, automated data analysis
- Very accurate and reliable
- Efficient (1-2 min per joint)
 - 200 or more joints can be tested in an 8-hr workday
 - Up to 3 lanes can be tested in a single pass



Expanding the Realm of Possibility


















Accuracy

- Conditions for best results
 - Depth: 150±40 mm
 - Horizontal & vertical misalignment: ±20 mm
 - Lateral placement error (side shift): ±50 mm
- Reported accuracy

Depth: ±4 mm
Rotation: ±4 mm
Side shift: ±8 mm
Repeatability: ±2 mm

⊕ARA


Expanding the Realm of Possibilit

Evaluation Results

- MIT specified accuracy was verified
- Overall standard deviation of measurement errors is estimated to be about 3 mm on rotation
 - Accurate to about ±5 mm at 95% confidence level

ARA

Expanding the Realm of Possibility





Dowel Bar Alignment in Typical Concrete Pavements


- Sponsored by American Concrete Pavement Association (ACPA)
- Objective evaluate and document the dowel bar alignment in typical concrete pavements
 - Evaluated typical-construction projects with no reported construction-related problems
 - Both DBI and basket sections were included
- MIT Scan-2 was used to measure dowel alignment


ARA


Expanding the Realm of Possibility





































Conclusions

- Dowel bar alignment can be determined very accurately and efficiently using MIT Scan
- There is a critical need to improve specifications on dowel placement tolerance
 - Must be consistent with field performance and pavement behavior
 - Consideration should be given to joint-by-joint evaluation
 - Identify conditions that will cause a joint to lock up
 - Determine the allowable number of locked joints
- With care good alignments can be obtained using either baskets or inserters



Expanding the Realm of Possibility