


I-285 Asphalt Shoulder Replacement with Roller Compacted Concrete Atlanta, GA



**Virginia Concrete Conference
March 10, 2006**

Project Location



Definition


“Roller-Compacted Concrete (RCC) is a no-slump concrete that is compacted by vibratory rollers.”

- Zero slump (consistency of damp gravel)
- No forms
- No reinforcing steel
- No finishing
- Consolidated with vibratory rollers



Concrete pavement placed in a different way!

Cement-Based Pavement Materials



Why Use RCC on I-285?

Ease of Placement



Durability



Successful Projects Elsewhere



Cost Effective



HEAVY TRUCK CORRIDOR





I-285 Prior to Construction



The Project

NHS – M001-00(534)01

17.3 miles of shoulder reconstruction with RCC, PCC slab replacement, various bridge joint replacements, and safety upgrades including guardrail, recovery zone improvements, rumble strips and wet reflective striping

The Project

Let: July 2004

■ RCC Subcontractor: A. G. Peltz – Birmingham, AL

■ Total Contract Price: \$20,168,734

RCC cost: \$ 4.3 million

■ Start Date: September, 2004

Completion Date: November, 2005

■ RCC Paving: October thru November, 2004

March thru early August, 2005

22 week-ends

Comparisons

- Total cost associated with RCC: Approx. \$8 million
 - Associated costs include grading, saw-cutting, joint sealing, etc.
 - RCC Contract Price: \$115 per cubic yard
- Cost if asphalt had been used: Approx. \$7.35 million
 - Based on estimated cost of \$42 per ton
- Differences:
 - RCC goes down in one lift and asphalt requires two or three lifts for same depth creating the need for more traffic control and additional time
 - Less impact to traveling public
 - Safer for workers and motorists
 - It is anticipated that RCC will have a useful life about two times that of asphalt resulting in lower long-term maintenance costs

Contract Specifics

- New shoulder width of 10 to 14 feet
- South of I-20, RCC six inches deep
- North of I-20, RCC 8 inches deep with 8 inches of GAB
- Contract calls for approx. 38, 500 cubic yards of concrete (203,000 sq. yds)
- Work hours restricted primarily to weekends
 - 9:00 p.m. Friday until 5:00 a.m. Monday
 - Holiday restrictions
- Traffic counts at approx. 140,000 ADT
- Truck Traffic: 15% (7000 trucks in OSL per day)

Typical Construction Schedule

- Removal of shoulders began Fri. Night at 9:00 PM.
- Typically removed between 1.5 and 2 miles.
- RCC placement began Sat. at 5:00 AM and continued until 6:00 PM. Began again Sun. at 5:00 Am and continued until completion.
- All lanes must be reopened by 5:00 AM Monday.

Design and Acceptance



RCC: Required 28-day Mix
Design Strength of 4,000 psi

Acceptance based on
density- 98% AASHTO T-
180 or 28-day core strenght
of 3500 psi

Core strength averaged
3980 psi

Cylinder strenght averaged
3964 psi

Design Loading Analysis

Table 1

Table 1				
RCC Thickness Required	Allowable Interior Load Repetitions Over Lifetime of RCC Pavement	Design Life in Years		
		20 yr	10 yr	5 yr
		Allowable Daily Repetitions		
5.5	25977	4	7	14
6	121504	17	33	67
6.5	432506	59	118	237
7	1000000	500	1000	2000

Old Material Removed



Old Material Removed



Base Prepared for Compaction



Base Ready for Compaction



Base Compacted



Concrete Plant



New Concrete Placed



New Concrete Placed



Material Placement



Spreader



Short Cure Rate



Initial Roller Compaction



Initial Roller Compaction



Roller Compaction

(rubber-coated drum)



Curing



Quality Control



Quality Control







Saw Cut Joints



Completed Shoulder



Joint Intersection



Rumble Strips



Finished Product



Finished Product





QUESTIONS OR COMMENTS