

Network for Success

Local Programs Workshop



Construction Documentation Breakout Session # 5 B Track - Project Development and Financials

Todd Stevens

District Construction Engineer, VDOT – Staunton

October 25, 2012

Network for Success
Local Programs Workshop



- **Daily Project Records**
- **Materials Records**
- **Discussion**

LAP Manual 13.1.5.1

Construction Administration

- **A daily diary of project activities must be kept for all federal-aid projects or projects to be maintained by VDOT.**
- **For non federal-aid projects which will be maintained by the LPA, project documentation supporting all payments for materials, price adjustments impacting reimbursements, and claims documentation must be kept on file and available for inspection for a minimum of three years after financial closure of the project.**

Why is project documentation important?

- **Provides a permanent record of the project**
- **Determines pay items/quantity of work**
- **Helps ensure the intent of the contract is enforced**
- **Prevents and defends against claims**
- **Provides transparency to the public**

Network for Success
Local Programs Workshop



Daily Project Records

What should be included in the daily records?

- **Date**
- **Weather**
- **Contractor's Equipment**
- **Contractor's Staff**
- **Work Items & Location**
- **Materials Delivered**
- **Pay Items/Quantity of Work**
- **All Communications (phone, e-mail, etc.)**
- **Safety**
- **Damage**
- **Visitors to the Job Site**
- **Delays (caused by utilities or other delays)**
- **Change Conditions**

If your project includes a schedule:

- **Deviations in approved and updated progress schedules as they compare to actual progress**
- **Changes in the logic or sequence of work**

Maintaining a log of schedule changes could be useful if a detailed analysis is required

Goals for Project Documentation: Seven Rights (7R's) of Quality Control:

- 1. The Right Material**
- 2. Put in the Right Way**
- 3. At the Right Time**
- 4. In the Right Place**
- 5. In the Right Quantities**
- 6. Having the Right Documentation**
- 7. Then, making the Right Payment to the Contractor.**

Effective documentation creates a clear and factual record of project events as they occur

- **Documentation must be prepared during the construction process – not afterward**
- **Documentation must be based in fact and not “opinion”**
- **Documentation must provide details**

With such records available, reasonable requests can be approved without delay and unreasonable requests can be successfully denied.

PROJECT DIARY ENTRY

Example No. 1

Said inspector told the contractor that the curb he installed last week on the southbound lane needed to be corrected before payment could be made.

SUGGESTED IMPROVEMENT

Example No. 1

I told Mr. Jones, the contractor's superintendent, that corrective action was needed on the CG-7 between Station 100+00 and Station 100+75 (left) due to local irregularities in the top of the curb exceeding 1" in 10 feet.

Advised the contractor that I need a plan for correction by 11-1-12.

No payment made due to defect.

PROJECT DIARY ENTRY

Example No. 2

Subcontractor on project trying for the fourth time to pour footer on Wall 5. I tried to talk to him about the rebar moving when he pours the concrete, but he told me not to tell him how to do his job and then said something that sounded like a swear under his breath.

SUGGESTED IMPROVEMENT

Example No. 2

Sub-contractor ABC, Inc. on the project today forming footer on Wall 5 at Station 200+10 (Rt.). The 3 previous times he tried to form the same footer he was unable to maintain the proper spacing on the rebar. I spoke with Mr. Smith, the contractor's superintendent, and discussed the requirement for maintaining bar spacing.

PROJECT DIARY ENTRY

Example No. 3

Spoke with contractor today about all the rain lately. Every time he gets ready for a pour, it rains. He said that if it keeps up he doesn't know how he is going to finish the project on time. I told him to keep trying.

SUGGESTED IMPROVEMENT

Example No. 3

Mr. Jones, the contractor's superintendent, alleged that the rain was affecting his concrete pours and if the rain keeps up he doesn't know how he is going to finish the project on time. I advised him that this was a fixed date contract and normal weather could not be given consideration for a time extension as per section 108.04 of the Road and Bridge Specifications.

Additional Information

- **LAP Manual, Chapter 13**
- **VDOT Construction Resource Guidebook**
- **VDOT Inspection Manual**
- **<http://www.virginiadot.org/business/construction/default.asp>**

Network for Success
Local Programs Workshop



Materials Records

What should be included in the material records?

- **Source of Materials**
- **Materials Notebook**
- **All Test Results**

Source of Materials

- **For Fed Aid and VDOT maintained projects, documentation of the source of the all materials is required**
- **Although not required, VDOT Form C-25 may be used to meet this requirement**

Materials Notebook

- **Should be initiated when construction begins**
- **The quantity of each material and the method of measurement shall be documented within the materials notebook**
- **The notebook must be kept up-to-date at all times and be made available to VDOT or FHWA personnel upon request**

Test Results

- **Test Reports for Materials**
- **Manufacturer's Certifications**
- **Field Density Tests**
- **Concrete Tests (Air, Slump, Compressive Strength)**

Additional Information

- **LAP Manual, Chapter 13.2**
- **VDOT Road and Bridge Specification**
- **VDOT Materials Manual of Instruction**
- **VDOT District Materials Section**

Network for Success
Local Programs Workshop



Discussion???

Network for Success

Local Programs Workshop



Construction Documentation Breakout Session #5 B Track – Project Development and Financials

Tammy Mancinelli

Civil Rights Compliance Coordinator, VDOT – Central Office

October 25, 2012

Required Civil Rights Project Documentation – Post Award

Program Areas and Responsibilities:

Locality and District Civil Rights Office (DCRO)

- **Equal Employment Opportunity (EEO) Compliance**
- **Disadvantage Business Enterprises (DBE) Compliance**

Locality

- **Labor Regulations Compliance**

Required Civil Rights Project Documentation – Post Award

Forms

- ✓ The forms in **red** can be found on the External Forms website for VDOT at:

<http://vdotforms.vdot.virginia.gov/>

Required Civil Rights Project Documentation – Post Award

Directly after Contract Execution

- ✓ Invite CR Representative to Pre-Construction Meeting
- ✓ EEO Program (Locality collects, tracks and provides copy to DCRO)
 - ✓ **C-64**
 - ✓ EEO Meeting Minutes
 - ✓ EEO Officer Designation
- ✓ DBE program (Locality collects, tracks and provides copy to DCRO)
 - ✓ Executed subcontracts between Prime and DBE firms
(listed on C-111 for DBE participation credit) within fourteen (14)
business days
 - ✓ Schedule of Participation

Required Civil Rights Project Documentation – Post Award

During Construction Phase

- ✓ EEO Program (Locality collects, tracks and provides copy to DCRO)
 - ✓ **C-57** – Project Specific – First three (3) months of activity on the project and annually for July (if active)
 - ✓ **Bulletin Boards** – Two (2) bulletin boards on project site to include the following posters:
 - ✓ EEO is the Law
 - ✓ **C-58** (False Statements)
 - ✓ **C-59** (Federal Wage Rates)
 - ✓ **C-60** (Non-Discrimination)
 - ✓ Wage Rates (from the Contract)
 - ✓ EEO Officer with contact information

Required Civil Rights Project Documentation – Post Award

During Construction Phase

- ✓ DBE Program (Locality collects, tracks and provides copy to DCRO)
 - ✓ Notify DCRO when DBE firm is expected to be performing work towards the Prime's participation credit
 - ✓ On-site locality inspector provides **Schedule B** for DBE Compliance Review to DCRO
 - ✓ Form **C-63** – reporting DBE and SWaM dollars physically paid to firms during the quarter – Due April 5th (Jan 1 – Mar 31), July 5th (Apr 1 – Jun 30),
October 5th (Jul 1 – Sep 30), Jan 5th (Oct 1 – Dec 31)

Required Civil Rights Project Documentation – Post Award

During Construction Phase

- ✓ Labor Compliance Program (Locality collects, tracks and ensures compliance with regulations)
 - ✓ Certified payroll (**WH347**) for each week of project activity for Prime contractor and all subcontractors, with Statement of Compliance (**C-56**) attached to each. Certified payroll is due two weeks after the end of the pay period.
 - ✓ Perform **Davis-Bacon Interview** within the first 30 days of project start, and quarterly thereafter
 - ✓ Compare information on Interview with certified payroll to ensure accuracy

Required Civil Rights Project Documentation – Post Award

Appendix 17A - Required Contract Provisions and Forms Matrix

Document	Applicable with Funding Source		Construction		Professional Services		Required in contract
	Federal	State	With Goal	W/O Goal	With Goal	W/O Goal	
FHWA 1273	•		•	•			•
EO 11246	•		•	•			•
USDOT 1050.2 Title VI Assurance Appendix A	•				•	•	•
Form C-28 - Basic Hourly Rate Paid By Contractor	•	•	•	•			
Form C-48 - Subcontractor/Supplier Solicitation and Utilization Form	•	•	•	•			•
Form C-49 - DBE Good Faith Efforts Documentation	•		•		•		•
(WH-347) Certified Payroll	•		•	•			
Form C-56 (WH-348) - Statement of Compliance	•		•	•			
Form C-57 -Highway Construction Contractors Monthly EEO Report	•	•	•	•			

Required Civil Rights Project Documentation – Post Award

QUESTIONS



Network for Success

Local Programs Workshop



Construction Documentation Breakout Session #5 B Track – Project Development and Financials

Jason Buys
October 25, 2012

Network for Success Local Programs Workshop



Run Time : 06:56:54

US Department Of Transportation Federal Highway Administration RASP5 Program Code Detail Listing (LF02U46A)

MONTH: 12 YEAR: 2011 BATCH NUMBER: 196

BATCH DATE	PRGM CODE	DEMO ID	REGION	STATE CODE	ACTVTY	PROJECT AGREEMENT	OBJECT	SCHEDULE NUMBER	TT	AMOUNT
12/16/2011	L290		00	51	50	5A27 1020	4100	000000	10	600.01
12/16/2011	L290		00	51	50	F509 0820	4100	000000	10	0.73
12/16/2011	L290		00	51	50	F509 0840	4100	000000	10	347,000.00
12/16/2011	L290		00	51	50	F509 1100	4100	000000	10	1,020.30
12/16/2011	L290		00	51	50	F509 1240	4100	000000	10	0.23
12/16/2011	L290		00	51	50	F509 1360	4100	000000	10	1.30
12/16/2011	L290		00	51	50	F509 1600	4100	000000	10	652.83
12/16/2011	L29E		00	51	50	0175 0100	4100	000000	10	1,185,048.77
12/16/2011	L29E		00	51	50	5111 2290	4100	000000	10	0.87
12/16/2011	L29E		00	51	50	5111 2360	4100	000000	10	1,408.62
12/16/2011	L29E		00	51	50	5127 0340	4100	000000	10	4,069.26
12/16/2011	L29E		00	51	50	5401 1870	4100	000000	10	1.40
12/16/2011	L29E		00	51	50	5403 0370	4100	000000	10	141,603.00
12/16/2011	L29E		00	51	50	5A03 2640	4100	000000	10	334,852.00
12/16/2011	L29E		00	51	50	5A27 0930	4100	000000	10	30.53
12/16/2011	L29E		00	51	50	5A27 0980	4100	000000	10	29.71
12/16/2011	L29E		00	51	50	5A27 0990	4100	000000	10	14.84
12/16/2011	L29E		00	51	50	5A27 1120	4100	000000	10	3,159.34
12/16/2011	L29E		00	51	50	5127 0550	4100	000000	10	111,479.00
12/16/2011	L29E		00	51	50	5A01 0020	4100	000000	10	58,998.54
12/16/2011	L29E		00	51	50	5A01 0100	4100	000000	10	213,366.01
12/16/2011	L29E		00	51	50	5A01 1810	4100	000000	10	83,503.37
12/16/2011	L29E		00	51	50	5A03 3430	4100	000000	10	0.00
12/16/2011	L29E		00	51	50	5A27 0020	4100	000000	10	403.72
12/16/2011	L240		00	51	50	0005 2290	4100	000000	10	124,136.48
12/16/2011	L240		00	51	50	0014 0120	4100	000000	10	4,026.61
12/16/2011	L240		00	51	50	0079 0990	4100	000000	10	0.78
12/16/2011	L240		00	51	50	0079 0790	4100	000000	10	1.01
12/16/2011	L240		00	51	50	0112 0200	4100	000000	10	0.95
12/16/2011	L240		00	51	50	0291 1020	4100	000000	10	0.00
12/16/2011	L240		00	51	50	0493 0350	4100	000000	10	0.00
12/16/2011	L240		00	51	50	0584 0220	4100	000000	10	0.00
12/16/2011	L240		00	51	50	0910 0170	4100	000000	10	0.00
12/16/2011	L240		00	51	50	0939 0090	4100	000000	10	0.00
12/16/2011	L240		00	51	50	2202 0050	4100	000000	10	0.00
12/16/2011	L240		00	51	50	5109 1190	4100	000000	10	7,706.20
12/16/2011	L240		00	51	50	5111 1280	4100	000000	10	0.00
12/16/2011	L240		00	51	50	5116 1760	4100	000000	10	476.91
12/16/2011	L240		00	51	50	5127 3760	4100	000000	10	0.00
12/16/2011	L240		00	51	50	5127 3820	4100	000000	10	0.00

B1



Commonwealth of Virginia
TRANSACTION RELATIONSHIP REPORT

Run Date: 02/07/2012
Run Time: 01:25 00

Business Unit: 50100 : VA Dept of Transportation
Invoice: FED000005
Project ID:
Contract Number: 5A01010

Page No. 1 of 2

813,395.11
.50
813,395.61 A1

.50 comes from additional transaction
detail at B3

Contract	Approp	Project ID	Analysis Type	Voucher	Timesheet	Expense	Journal	Accounting Date	Expenditure Amount	Billed Amount
5A01010	L23R									\$813,395.11
		0000094904	CNV				0000781810	11/28/2011	40.25	32.20
		0000094904	CNV				0000781810	11/28/2011	12.95	10.36
		0000094904	CNV				0000781810	11/28/2011	112.42	89.94
		0000094904	CNV				0000781807	11/28/2011	79.80	63.84
		0000094904	CNV				0000781807	11/28/2011	28.57	22.86
		0000094904	CNV				0000781807	11/28/2011	9.20	7.36
		0000094904	CNV				0000781794	11/29/2011	10.01	8.01
		0000094904	CNV				0000781794	11/29/2011	3.22	2.58
		0000094904	CNV				0000781794	11/29/2011	27.97	22.38
		0000094904	CNV				0000781795	11/29/2011	58.22	46.58
		0000094904	CNV				0000781795	11/29/2011	18.74	14.99
		0000094904	CNV				0000781795	11/29/2011	162.59	130.07
		0000094904	CNV				0000781804	11/28/2011	32.05	25.64
		0000094904	CNV				0000781804	11/28/2011	10.31	8.25
		0000094904	CNV				0000781804	11/28/2011	89.52	71.62
		0000094904	CNV				0000781812	11/28/2011	21.51	17.21
		0000094904	CNV				0000781812	11/28/2011	6.92	5.54
		0000094904	CNV				0000781812	11/28/2011	60.07	48.06
		0000094904	CNV				0000781796	11/29/2011	1.01	0.81
		0000094904	CNV				0000781796	11/29/2011	0.32	0.26
		0000094904	CNV				0000781796	11/29/2011	2.81	2.25
		0000094904	CNV				0000781797	11/29/2011	8.47	6.78
		0000094904	CNV				0000781797	11/29/2011	26.32	21.06
		0000094904	CNV				0000781797	11/29/2011	73.51	58.81
		0000094904	CNV				AP00781532	11/22/2011	563,540.84	450,832.67
		0000094904	CNV				AP00781532	11/22/2011	450,092.93	360,074.34
		0000094904	CNV				AP00781583	11/23/2011	644.62	515.70
		0000094904	CNV				DC00781637	11/28/2011	12.75	10.20
		0000094904	CNV				DC00781637	11/28/2011	5.75	4.60
		0000094904	CNV				TR00781521	11/22/2011	529.35	423.48
		0000094904	CNV				TR00781675	11/30/2011	34.20	27.36
		0000094904	CNV				TR00781286	11/16/2011	45.60	36.48
		0000094904	CNV				TR00781286	11/16/2011	9.88	7.90
		0000094904	CNV				TR00781720	11/30/2011	354.95	283.96
		0000094904	CNV				TR00781720	11/30/2011	461.97	369.58
		0000094904	CNV				TR00781519	11/22/2011	114.23	91.38

Actual amount of the expenditure includes
state and local match per federal
requirements.
Actual amount of federal expenditure is
80% of the full amount.

C1

Network for Success Local Programs Workshop



<u>Contract</u>	<u>Approp</u>	<u>Project ID</u>	<u>Analysis Type</u>	<u>Voucher</u>	<u>Timesheet</u>	<u>Expense</u>	<u>Journal</u>	<u>Accounting Date</u>	<u>Expenditure Amount</u>	<u>Billed Amount</u>
Total									\$1,016,743.83	\$813,395.11
Total Amount Billed for FED000005									\$ 1,016,743.83	\$813,395.11

Network for Success Local Programs Workshop



Commonwealth of Virginia
TRANSACTION RELATIONSHIP REPORT

Run Date: 02/07/2012
Run Time: 01:24 00

Report ID: RPA145

Page No. 1 of 1

Business Unit: 50100 : VA Dept of Transportation
Invoice: FED000004
Project ID:
Contract Number: SA01010

<u>Contract</u>	<u>Approp</u>	<u>Project ID</u>	<u>Analysis Type</u>	<u>Voucher</u>	<u>Timesheet</u>	<u>Expense</u>	<u>Journal</u>	<u>Accounting Date</u>	<u>Expenditure Amount</u>	<u>Billed Amount</u>
5A01010	L23R	0000094904	CNV				0000732665	05/02/2011	(0.05)	\$ 0.50
		0000094904	CNV				0000779012	10/06/2011	(288.88)	(0.04)
		0000094904	CNV				AP00779274	10/15/2011	0.61	(231.10)
		0000094904	CNV				0000732665	05/02/2011	0.05	0.49
		0000094904	CNV				0000780455	10/30/2011	0.01	0.04
		0000094904	CNV				AP00773965	07/07/2011	0.01	0.01
		0000094904	CNV						288.88	231.10
Total									\$ 0.62	\$ 0.50
Total Amount Billed for FED000004									\$ 0.62	\$ 0.50

End of Report



I. COMPLETE INVOICE INFORMATION		Location:	Manassas
Vendor Name:	██████████ County	Vendor ID:	0000033642 Resp ORG: _____
Invoice Receipt Date:	10/31/11	Invoice #:	PWC400213P11 <small>(must be 10 digits)</small>
Goods Receipt Date:	09/30/11	Invoice Date:	10/24/11 <small>*(12 space max. - ALL CAPS no punctuation)</small>
Requisition #	_____	Gross Amo C2	\$563,540.84 B1
PO #:	_____	Account #:	_____ <small>*(15 space max. - ALL CAPS no punctuation)</small>
Receiving #:	_____	Description:	Rte 1 S Improvement Project <small>*(22 space max.)</small>
Contract #:	_____ <small>(must be 18 digits)</small>	BOLDED items with (*) appear on vendor check	

Document Type (Check One)

<input type="checkbox"/> Vendor Invoices (PO Related)	<input type="checkbox"/> IAT (PO Related)
<input checked="" type="checkbox"/> Vendor Invoices (Non PO Related)	<input type="checkbox"/> IAT (Non PO Related)
<input type="checkbox"/> Consultant Invoice	<input type="checkbox"/> Petty Cash (PO Related)
<input type="checkbox"/> Contractor Payment Voucher	<input type="checkbox"/> Petty Cash Invoice (Non PO Related)

II. COMPLETE ACCOUNTING DISTRIBUTION INFORMATION

Catg.™	Speed Type	Account	Amount	County	Asset Type	Route	Structure	Facility	Bldg/Lot
UPC	94904	1431	563,540.84						
Activity	MP From	MP To	Parcel	Operational Project	EMS W/O	Equip ID	Org.	Contract ID	Bond#
631									
Catg.™	Speed Type	Account	Amount	County	Asset Type	Route	Structure	Facility	Bldg/Lot
Activity	MP From	MP To	Parcel	Operational Project	EMS W/O	Equip ID	Org.	Contract ID	Bond#

*RTE = Route, CSC = Cost Center, W/O = Equipment Work Order, UPC = Universal Project Number

Special Instructions: (check if applicable)

Send to DOA as Batch Type 'X' (check comes back to VDOT for special handling)

Other _____

Certification Statement for Preparer: I certify that the related goods / services are appropriately documented as received; and that the invoiced amounts are correctly calculated.		Certification Statement for Approver: I certify that this expenditure is necessary to the conduct of business on behalf of the Commonwealth; and that the invoiced amounts are appropriately charged.	
Prepared by John Flemming		Approved by Susan Shaw	
	11/15/11		11/15/11
Prepared by Signature	Date	Approved by Signature	Date

III. COMPLETE VOUCHER INFORMATION

Date Entered: 11/14/11

Voucher #: 2733448
(must be seven digits)

Entered By: Trudee Hunter

FISCAL USE ONLY

Final Approval By _____

Date _____

C1

Network for Success Local Programs Workshop



CONTRACTOR'S REQUEST FOR PAYMENT

CONTRACT NO. 11059B00 PO # PO110239

CONTRACT DATE 9/14/2010 INVOICE DATE 9/30/2011

REQUEST FOR PAYMENT NO. 12

SUBMISSION OF (CHECK ONE)

 PROGRESS PAYMENT SEMI-FINAL PAYMENT

NOTE: SUBMISSION OF FINAL APPLICATION FOR PAYMENT SHALL BE FOR RETAINAGE ONLY

ORIGINAL CONTRACT AMOUNT	<u>7,422,236.00</u> ✓
CHANGE ORDERS	<u>51,295.01</u> ✓
ADJUSTED CONTRACT AMOUNT INCLUDING CHANGE ORDERS	<u>7,473,531.01</u> ✓
(1) ORIGINAL WORK EARNED	<u>4,813,915.88</u> ✓
(2) CHANGE ORDER WORK EARNED	<u>19,599.82</u> ✓
(3) MATERIAL ON HAND	<u>9,473.04</u> ✓
(4) MATERIAL ADJUSTMENTS (type)	<u> </u>
(5) TOTAL AMOUNT EARNED (1+2+3+4)	<u>4,842,988.64</u> ✓
(6) RETAINAGE WITHHELD YEAR-TO-DATE (line 5*5%) max 185,555.90	<u>185,555.90</u> B
(7) RETAINAGE WITHHELD THRU LAST REQUEST	<u>185,555.90</u> ✓
(8) RETAINAGE WITHHELD CURRENT (6-7)	<u> </u> ✓
(9) AMOUNT PREVIOUSLY INVOICED	<u>4,113,838.79</u> ✓
(10) AMOUNT DUE THIS INVOICE (5-8-9)	<u>543,595.95</u> C2

CONTRACTOR SIGNATURE Signed *A.W. Brown*

OWNER/COUNTY ACTION:

COUNTY RESIDENT ENGINEER Signed *[Signature]*

Approved by: ██████████ County

DATE 10/11/11 Signed *[Signature]*

Network for Success Local Programs Workshop



_____ County
Route / Improvements Phase II - Roadway Construction
No. 1P1110304
VDOT NO. RSTP-0421 (0101), 0801-ETS-R110301, UPC94804

Payment Request

ITEM	DESCRIPTION	UNIT	CONTRACT QTY	UNIT PRICE	EXTENDED COST	TOTAL QUANTITY TO PREVIOUS MONTH	Progress (Estimated Period Ending Request Payment No.			JOB TO DATE QUANTITIES	JOB TO DATE AMOUNT
							TOTAL AMOUNTED PREVIOUS MONTH	THIS MONTH QUANTITY	THIS MONTH AMOUNT		
											6/30/2011 12
1.00	MOBILIZATION	1.00 LS		510,000.00	510,000.00	0.79	401,111.80	0.00	0.00	0.79	401,111.80
2.00	CONSTRUCTION SURVEYING	1.00 LS		45,000.00	45,000.00	0.84	38,094.00	0.00	1,814.00	0.88	38,908.00
3.00	CLEARING & GRUBBING	1.00 LS		25,000.00	25,000.00	1.00	25,000.00	0.00	0.00	1.00	25,000.00
4.00	REGULAR EXCAVATION	39,801.00 CY		18.00	711,818.00	38,132.27	680,368.58	1,000.00	18,000.00	37,132.27	668,368.58
5.00	UNDERCUT EXCAVATION - CT	3,000.00 CY		0.33	300.00	3,447.28	317.00	880.00	300.00	4,127.88	619.10
6.00	SELECT MATERIAL TYPE I MIN	17,800.00 CY		2.33	28,460.00	3,432.64	7,267.38	180.38	323.28	3,852.32	7,690.45
7.00	MINOR STRUCTURE EXCAV. B	1,811.00 CY		40.00	72,440.00	880.89	34,438.80	309.11	13,864.40	1,290.00	48,000.00
8.00	REMOVE AND DISPOSE EXIST	1.00 LS		20,000.00	20,000.00	0.00	18,800.00	0.00	0.00	0.00	18,800.00
9.00	REMOVE AND DISPOSE EXIS	1.00 LS		25,000.00	25,000.00	0.00	6,250.00	0.00	7,500.00	0.00	13,750.00
10.00	GEOTEXTILE (SLURGRADE STA	17,812.00 SY		1.80	32,061.60	13,587.11	20,758.51	2,714.78	5,158.08	18,271.89	30,918.59
11.00	AGGREGATE BEDDING MATER	1,000.00 TON		21.35	21,350.00	0.00	0.00	70.54	1,579.68	70.54	1,579.68
12.00	BEDDING MATL AGGRWD. 3/8 S	738.00 TON		18.85	13,799.30	487.85	9,434.20	0.00	0.00	487.85	9,434.20
13.00	NO. 3 DR 3 AGGR.	2,183.00 TON		26.00	56,758.00	2,577.23	64,436.70	70.32	1,758.00	2,647.55	66,188.75
14.00	PRECAST BOX CULVERT (30X	362.00 LF		1,050.00	380,100.00	143.00	149,100.00	78.00	81,800.00	220.00	231,000.00
15.00	CONCRETE CLASS A3	7.00 CY		1,190.00	8,330.00	0.00	0.00	0.00	0.00	0.00	0.00
16.00	FLOWABLE BACKFILL - CONTE	80.00 CY		287.00	22,960.00	3.00	801.00	0.00	0.00	3.00	801.00
17.00	UNDERDRAIN U0-3	1,100.00 LF		21.40	23,540.00	0.00	0.00	0.00	0.00	0.00	0.00
18.00	UNDERDRAIN U0-3	1,704.00 LF		21.40	36,465.60	0.00	0.00	878.00	18,728.00	878.00	18,728.00
19.00	UNDERDRAIN U0-4	5,300.00 LF		11.25	59,625.00	3,857.00	44,730.20	0.00	0.00	3,857.00	44,730.20
20.00	CONC. UNDERDRAIN U0-3	128.00 LF		18.00	2,304.00	0.00	0.00	0.00	0.00	0.00	0.00
21.00	OUTLET PIPE	200.00 LF		10.70	2,140.00	80.00	841.00	0.00	0.00	80.00	841.00
22.00	18" CONC. PIPE	1,888.00 LF		53.70	101,281.60	1,871.00	100,472.70	0.00	0.00	1,871.00	100,472.70
23.00	18" RADIAL CONC. PIPE	158.00 LF		53.70	8,482.60	0.00	0.00	0.00	0.00	0.00	0.00
24.00	18" CONCRETE PIPE	288.00 LF		80.00	23,040.00	288.00	17,350.00	0.00	0.00	288.00	17,350.00
25.00	24" CONCRETE PIPE	700.00 LF		85.00	59,500.00	689.00	58,700.00	0.00	0.00	689.00	58,700.00
26.00	30" CONCRETE PIPE	610.00 LF		80.00	48,800.00	540.00	40,820.00	0.00	0.00	540.00	40,820.00
27.00	36" CONC. PIPE	1,481.00 LF		138.00	204,258.00	1,481.00	172,098.00	0.00	0.00	1,481.00	172,098.00
28.00	42" CONC. PIPE	458.00 LF		158.00	72,564.00	441.00	69,798.00	0.00	0.00	441.00	69,798.00
29.00	24" END SECTION ES-1	3.00 EA		881.00	2,643.00	0.00	1,760.00	0.00	0.00	0.00	1,760.00
30.00	30" END SECTION ES-1	1.00 EA		1,148.00	1,148.00	1.00	1,148.00	0.00	0.00	1.00	1,148.00
31.00	42" END SECTION ES-1	3.00 EA		1,841.00	5,523.00	1.00	1,841.00	0.00	0.00	1.00	1,841.00
32.00	DROP INLET D138, L=4'	3.00 EA		2,542.00	7,626.00	0.00	7,626.00	0.00	0.00	0.00	7,626.00
33.00	DROP INLET D138, L=8'	13.00 EA		2,982.00	38,766.00	11.00	32,882.00	0.00	0.00	11.00	32,882.00
34.00	DROP INLET D138, L=8'	6.00 EA		2,982.00	17,892.00	0.00	14,410.00	0.00	0.00	0.00	14,410.00
35.00	DROP INLET D138, L=12'	6.00 EA		3,300.00	19,800.00	4.00	13,200.00	0.00	0.00	4.00	13,200.00
36.00	DROP INLET D138, L=12'	1.00 EA		3,127.00	3,127.00	0.00	0.00	0.00	0.00	0.00	0.00
37.00	DROP INLET D138, L=8'	1.00 EA		4,002.00	4,002.00	1.00	4,002.00	0.00	0.00	1.00	4,002.00

Network for Success Local Programs Workshop



██████████ COUNTY
Route 1 Improvement Project

PROJECT DIARY - DAILY GENERAL SHEET

Page No. _____

Day Thursday Date 05/03/11
 Weather Sunny A.M. 7:00 P.M. 3:30
 Temperature warm Low 83 High 78
 Prime Contractor Worked: Hours 7:00 A.M. To: 3:30 P.M.
 Project Number: SES18004
 Contractor: ASW Contracting Co.
 Sub-Contractor: _____

Labor: Laborers <u>7</u> Operators <u>5</u> Foreman <u>2</u> Superintendent <u>1</u>	Equipment: Active Samsung Excavator with Hammer, 320 Excavator D-5 Dozer, 950 Loader, Cat Rubber tired loader
---	--

Comments:
 ASW busy busting out the old existing box culverts and hauling the debris to the county landfill. There really is not too much activity taking place on the project site other than the demolition and some operators moving dirt around. ASW stockpiling of #3 stone. ASW still has the V.M.S. boards at Brady's Hill Rd.

Item#	Description	Unit	Quantity	Location
0	Removing Drainage structure	LS	0.3	Taking out section of box culvert
10	# 3 Aggregate	Tn	70.00	Stone Stockpile for box culverts
81	Group H Churnmaking Devices	Day	340	Project Wide
82	V.M.S.	Hrs	48	one H.B.L., one S.B.L., 340 Hrs

* Equipment Note
 Crane, 400 lbcr, backhoe


Signed George M. Shestey
 Inspector Keeping This Diary
 Approved [Signature]
 By Initials Project Engineer

Network for Success Local Programs Workshop

VDOT Virginia Department of Transportation

Ray Item #9

4/22/11



Approx. 200 LF of existing box total, about 85' removed which is approximately equal to 43%.

Network for Success Local Programs Workshop



Virginia Department Of Transportation Weighperson's Daily Summary

This is to certify that VAcon Materials STAFFORD
(Company Name) (Plant Location)

Shipped the following materials on the below referenced date

Date: 9/12/2011
 Project: 0001-075-R11-0001
 Route: 0001
 County: [REDACTED]
 Type Material: VA 457 Quality Assurance
 Job Mix ID: _____

Lot Number: _____ Modified Acceptance Program
 Loads: 3
 Total English Tons: 73.54
 Total Metric Tons: 66.71
Jenny McDev
 (Bonded Weighmaster)

DEPARTMENT USES ONLY

Department's Verification
 Date: 9/16/11
 No. Loads Received: 3
 Reason For Difference: _____
 English Tons Received: 73.54
 Metric Tons Received: _____
 English Tons Deducted: _____
 Metric Tons Deducted: _____
 Total Tons: 73.54

Leonard H. Coleman RECEIVED 9/16/11 Engineer
 (Department Representative) (Title)

Department Representative has verified quantities and recorded pertinent information from the weigh tickets or certified delivery tickets.

Network for Success Local Programs Workshop



OPEN GRADED AGGREGATE - VA #57							
ITEM NO.	DATE MATL. RECEIVED	ACCEPTANCE METHOD	SIZE	QUANTITY (TONS)	PLANT	PLANT LOCATION	COMMENTS
11	9/12/2011	QA	VA #57	73.54	Vulcan	Stafford, VA	Route 1 Sta. 232+00 to 235+00 (NBL) Sidewalk over UD-3
Total				73.54 TONS			
SUMMARY							
11	-	-	VA #57	73.54 TONS	-		

Network for Success Local Programs Workshop



ITEM	DESCRIPTION	UNIT	CONTRACT CITY	UNIT PRICE	EXTENDED COST	TOTAL QUANTITY TO PREVIOUS MONTH	Progress Estimated Period Ending Request Payment No.				JOB TO DATE QUANTITIES	JOB TO DATE AMOUNT	
							TOTAL AMOUNT TO PREVIOUS MONTH	THIS MONTH QUANTITY	THIS MONTH AMOUNT	Request Payment No.			
												9/30/2011	13
39.00	OROP INLET DI-399, L=8'	1.00 EA		3,318.00	3,318.00	1.00	3,318.00	0.00	0.00	1.00	3,318.00		
39.00	OROP INLET DI-399, L=10'	1.00 EA		4,336.00	4,336.00	1.00	4,336.00	0.00	0.00	1.00	4,336.00		
40.00	OROP INLET DI-3C, L=10'	3.00 EA		3,133.00	8,266.00	3.00	8,266.00	0.00	0.00	3.00	8,266.00		
41.00	OROP INLET DI-49, L=8'	2.00 EA		3,858.00	7,716.00	3.00	11,574.00	0.00	0.00	3.00	11,574.00		
42.00	OROP INLET DI-49, L=10'	1.00 EA		4,189.00	4,189.00	1.00	4,189.00	0.00	0.00	1.00	4,189.00		
43.00	OROP INLET DI-499, L=8'	1.00 EA		4,811.00	4,811.00	1.00	4,811.00	0.00	0.00	1.00	4,811.00		
44.00	OROP INLET DI-499, L=10'	3.00 EA		4,803.00	14,409.00	3.00	14,409.00	0.00	0.00	3.00	14,409.00		
45.00	OROP INLET DI-499, L=12'	1.00 EA		4,378.00	4,378.00	1.00	4,378.00	0.00	0.00	1.00	4,378.00		
46.00	OROP INLET DI-10A, L=8'	1.00 EA		3,838.00	3,838.00	0.00	0.00	0.00	0.00	0.00	0.00		
47.00	OROP INLET DI-10A, L=8'	1.00 EA		3,848.00	3,848.00	1.00	3,848.00	0.00	0.00	1.00	3,848.00		
48.00	OROP INLET DI-10A, L=12'	1.00 EA		8,870.00	8,870.00	3.00	11,740.00	0.00	0.00	3.00	11,740.00		
49.00	OROP INLET DI-10C, L=8'	3.00 EA		2,301.00	4,702.00	3.00	4,702.00	0.00	0.00	3.00	4,702.00		
50.00	OROP INLET DI-10C, L=8'	1.00 EA		3,862.00	3,862.00	1.00	3,862.00	0.00	0.00	1.00	3,862.00		
51.00	MANHOLE MHT	11.00 LF		878.00	10,657.30	8.80	8,317.30	0.00	0.00	8.80	8,317.30		
52.00	FRAME & COVER MH-1	3.00 EA		481.00	882.00	1.00	481.00	0.00	0.00	1.00	481.00		
53.00	W/RS CONTR STONE CL. AL-1	7.00 SF		87.50	673.50	10.00	875.00	0.00	0.00	10.00	875.00		
54.00	W/RS CONTR STONE CL. 1.00	248.00 SF		67.50	16,800.00	83.10	8,284.30	0.00	0.00	83.10	8,284.30		
55.00	AGGR BASE MATL TY-1 HD-31H	14,734.00 TON		20.00	294,680.00	10,087.58	301,381.80	1,331.84	28,236.80	16,376.45	327,588.60		
56.00	ASPHALT CONCRETE TY. BM-1	8,104.00 TON		61.40	313,366.40	1,488.71	68,088.08	1,317.90	74,742.32	2,884.61	184,801.90		
57.00	ASPH CONC BASE CR TY BM-2	21,982.00 TON		57.50	1,213,171.00	8,033.78	462,744.58	2,322.85	133,768.18	10,356.63	595,540.74		
58.00	FLEXIBLE PAVEMENT PLANNING	11,881.00 SF		1.00	11,881.00	0.00	0.00	0.00	0.00	0.00	0.00		
59.00	ASPHALT CONCRETE TY. BM-4	448.00 TON		87.50	39,200.00	0.00	0.00	20.14	2,034.76	20.14	2,034.76		
60.00	ASPHALT CONCRETE TY. BM-4	4,288.00 TON		67.24	274,885.12	0.00	0.00	0.00	0.00	0.00	0.00		
61.00	STD. CURB C&G	130.00 LF		18.00	2,340.00	0.00	0.00	0.00	0.00	0.00	0.00		
62.00	RADIAL CURB C&G	34.00 LF		17.00	578.00	0.00	0.00	0.00	0.00	0.00	0.00		
63.00	STD. CORR. CURB & GUTTER	8,827.00 LF		18.50	163,098.50	3,113.88	32,752.90	0.00	77.50	3,191.38	32,830.40		
64.00	RADIAL CORR. CURB & GUTTER	1,082.00 LF		18.00	19,476.00	333.80	3,860.00	0.00	0.00	333.80	3,860.00		
65.00	STD. CORR. CURB & GUTTER	332.00 LF		18.50	3,641.00	193.30	2,881.70	0.00	0.00	193.30	2,881.70		
66.00	RADIAL CORR. CURB & GUTTER	80.00 LF		18.00	1,440.00	88.30	1,104.00	0.00	0.00	88.30	1,104.00		
67.00	COL. 12 DETECTABLE WARNING	45.00 SF		315.00	8,875.00	0.00	0.00	4.00	860.00	4.00	860.00		
68.00	HYDR. CEMENT CONC SIDW	2,158.00 SF		31.50	68,081.00	0.00	0.00	330.40	17,217.40	330.40	17,217.40		
69.00	DIRECTIONAL ISLAND CURB(S)	128.00 LF		15.00	1,920.00	108.00	1,620.00	0.00	780.00	181.00	2,410.00		
70.00	IMPACT ATTENUATOR SER. T	34.00 EA		1,821.00	61,914.00	3.00	5,763.00	3.00	5,760.00	6.00	11,523.00		
71.00	MEDIAN STRIP MS-1	731.00 SF		65.00	47,515.00	0.00	0.00	0.00	0.00	0.00	0.00		
72.00	MEDIAN STRIP MS-2	1,099.00 LF		30.00	32,970.00	0.00	0.00	0.00	0.00	0.00	0.00		
73.00	GUARDRAIL GR-3	82.00 LF		25.50	2,091.00	0.00	0.00	0.00	0.00	0.00	0.00		
74.00	RAD. GUARDRAIL GR-2	118.00 LF		37.50	4,417.50	0.00	0.00	0.00	0.00	0.00	0.00		
75.00	ALTERNATE BREAKWAY CAB	4.00 EA		3,348.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00		
76.00	TEMP. SAFETY FENCE #	1,482.00 LF		0.88	1,103.76	660.00	760.00	0.00	0.00	660.00	760.00		
77.00	ALWAYING GUST	702.00 HR		1.10	772.20	33.00	35.30	4.80	4.80	37.80	35.30		
78.00	CONSTRUCTION SIGNS	785.00 SF		18.00	14,130.00	785.00	12,740.00	0.00	780.00	785.00	12,740.00		
79.00	TRUCK MOUNTED ATTENUATORS	300.00 HR		5.50	1,650.00	0.00	0.00	0.00	0.00	0.00	0.00		
80.00	TYPE III BARRICADE	14.00 EA		374.00	5,236.00	2.00	748.00	2.00	748.00	4.00	1,496.00		
81.00	GROUP 2 CHANNEL DRAIN DEV	28,900.00 DAY		0.55	15,895.00	26,431.00	15,187.00	6,384.00	3,811.30	30,816.30	19,698.30		

Network for Success Local Programs Workshop



_____ COUNTY
Route 1 Improvement project

PROJECT DIARY - DAILY GENERAL SHEET

Page No. _____

Day Monday Date 9/12/2011
 Weather Sunny A.M. 7:00 P.M. 3:30
 Temperature None Low 62 High 83
 Prime Contractor Worked: _____ Hours 7:00AM To 7:00 PM
 Project Number: 808130084
 Contractor: ASW Contracting Co.
 Sub-Contractor: A-Team

Labor: _____ Equipment: Active
 Laborers 8
 Operators 8
 Foreman 2
 Superintendent _____

Comments:
 I was off on sick leave today so nothing to add to diary other than Quantities

Item#	Description	Unit	Quantity	Location
11	# 87 Stone	Tn	73.54	Sta. 232 to 238 N.S. SW underdrain
83	Bit Comb. Curb & Gutter CG-8	LF	5	Sta. 232
87	CG-12 Detectable Warning Surface SF		4	Directional Island at Fuller
88	Hyd. Cement Conc. Sidewalk 4"	Sq	249	Sta. 232 to 238+00 N.S.L.
89	Directional Island Curb CG-2	LF	52	At Fuller & Rt 1
91	Group of Channeling Devices	Day	140	Project Wide
92	VMS	Hrs	48	2 at 24 hrs each for traffic switch
100	Station Excavator	CY	26	This Cut site
101	Silt Fence	LF	48	where needed on site

* Equipment title

Signed George M. Stepien
 Inspector Keeping This Diary
 Approved [Signature]
 By Initials [Signature] Project Engineer
See MAP daily report

Network for Success
Local Programs Workshop



9/12/11

249 SY Concrete

232+00

Stations
235+00

Hydraulic 4" concrete sidewalk x 6' x 300'
5" stone base for sidewalk

Measured by
George M. Sheesley
G. M. Sheesley

Network for Success Local Programs Workshop



No. 1 (revised) September 2011

██████████ COUNTY
Route 1 Improvement Project

PROJECT DIARY - DAILY GENERAL SHEET

Page No. _____

Day	Friday	Date	September 2, 2011
Weather	Overcast	A.M. 7:00	P.M. 2:00
Temperature		Low 55	High 81
Prime Contractor Worked		Hours 7:00 AM	To 3:30 PM
Project Number	PR110004		
Contractor	ASW Contracting Co.		
Sub-Contractor	Cardozo Concrete Co.	A-Team Excavating	
Labor:			
Laborers	9	Equipment: Active	
Operators	9	D-5 Dozer, 450 Dozer, 953 Loader	
Foremen	2	Cat Rubber tired loader	
Superintendent			

Comments:

This morning at 10:00 A.M had meeting with Ms. Al, Kevin, Charles & myself regarding the asphalt around the Monument area and if it was put in to heavy and when they saw out if there was too much asphalt wasted when they saw out. Decision was not made at this time. Cardozo concrete on project site to pour concrete sidewalks they had concrete set up for 12 noon and they ordered their last truck at 3:15 P.M with traffic getting heavy. They were late getting it poured out ASW grading crews working on the S.B.L. side around stations 253+00 to 254+00 and the A team were on N.B.L. side placing underdrain where the sidewalks are to go. The other ASW grading crew placing stone for the concrete sidewalks. Virginia paving sub contractor Fredericksburg signed mobilized their paving machine onto the project site today so it will be ready for the day after labor day.


Item	Description	Unit	Quantity	Location
14	Underdrain UD-3	LF	575	Sta 240+00 to 249+00
55	21" Aggregate	Tn	140.08	Sta. 237+00 to 254+00
81	Group B Channeling Devices	Day	140	Project Wide
82	V.M.S. Boards	Pcs	48	Rt 1 N.B.S.S. S. lanes 2X24 lanes
180	Junction Box JB 5' 2	Ca	11	Rt1&Square, Rt1 & Joplin
180	3" Conduit	LF	585	Rt1&Square, Rt1 & Joplin
188	4" Conduit	LF	70	Rt1&Square, Rt1 & Joplin
187	Thatch Excavation	LF	955	Rt1&Square, Rt1 & Joplin
203	Bored Conduit 4"	LF	110	Rt1&Square, Rt1 & Joplin
68	Hydr. Cement Conc. Sidewalk 4"	Sy	300	228+50 N 230+00 N.B.L.

* Equipment Idle
ALL OTHER EQUIPMENT IDLE

Signed: George M. Shewley
Inspector Keeping This Diary

Approved By: [Signature]
Project Engineer

Network for Success Local Programs Workshop



#68
Hydraulic
Concrete
Sidewalk

4" Depth X 6' wide X 350' with
5" Stone base compacted

Network for Success Local Programs Workshop



Project Documentation Breakout Session #5 - B Track – Project Development and Financials

Jeffrey W. Everton C.P.I.I.

Construction Inspection Supervisor, City of Newport News

October 25, 2012

City of Newport News Best Practices Civil Construction Inspections

- Inspection Program
- Created in house by GIS Programmer
- Web-based Application
- Daily/Weekly/Monthly Reporting
- Tracks Activities and Materials
- Monthly Billing